BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
EE/YNK/BBMP/E-PMT/01/2017-18 Dated: 11-04-2017

APPROVED TENDER SCHEDULE –'B'

Item No: 01

Name of Work:- Construction of Karaga Mantapa at Yelahanka lake in ward No:01 of Yelahanka sub division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri RAMESH Y B	
				Rate	Rate in Words
1	KSRRB M200-24:- dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces no exceeding 0.02 Cum in volume and stock piling at designated locations and disposal of dismantled materials upto a lead of 1000 meters, stacking serviceable and unserviceable materials separately complete as per specifications.MORTH specifications. No. 202, (P.No. 138/ Item No. 18.47)	Sqm	132.60	843.48	Rupees eight hundred forty three and paise forty eight only
2	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (a) / 2.3.1 (P.5/I.2.1)	Cum	60.00	169.56	Rupees one hundred sixty nine and paise fifty six only
3	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No.5/Item No. 2.3)	Sqm	271.13	204.12	Rupees two hundred four and paise twelve only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contrac... Approved Rates Sri RAMESH Y B	
				Rate	Rate in Words
4	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No.17.1)	Cum	463.73	100.00	Rupees one hundred only
5	KSRB 5.1-2 : Providing and constructing granite / trap / basalt rubble stone masonry in foundation with cement mortar 1:6 (Uncoursed), bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.12 (Page No.23/ Item No.5.3)	Sqm	62.57	3508.92	Rupees three thousand five hundred eight and paise ninety two only
6	KSRRB M2100-10. Plain cement concrete M10 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @ 0.84cum and fine aggregates @ 0.56cum in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14days complete as per specifications. MORTH Specification No.2100(P.No.218 & It.No.27.18)	Cum	75.64	6084.72	Rupees six thousand eighty four and paise seventy two only
7	KSRRB M2200-5.14 : Design mix M30 with OPC cement @ 360kgs , with 20mm and down size graded granite metal,coarseaggregated @ 0.69cum ,and fine aggregated @ 0.46cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed -2008 (P.No.224/ I.No.28.7.15)	Sqm	121.35	7550.28	Rupees seven thousand five hundred fifty and paise twenty eight only
8	KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (Page No. 23/ Item No. 5.6)	Sqm	9.68	4521.96	Rupees four thousand five hundred twenty one and paise ninety six only
9	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) M20 for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, for raft foundation, column footing, main and secondary beams with all lead and lifts etc.,complete (exclusive of cost of steel and fabrication charges.)Page No.13/Item No.4.49.3)-do- M30	Cum	70.00	6742.44	Rupees six thousand seven hundred forty two and paise forty four only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri RAMESH Y B	
				Rate	Rate in Words
10	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 -do- TMT Bars Fe 550 P.17/It.No.4.46.3	Sqm	19.6487	61237.08	Rupees sixty one thousand two hundred thirty seven and paise eight only
11	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6. (Page No. 16/ Item No. 4.32)	Cum	89.64	395.28	Rupees three hundred ninety five and paise twenty eight only
12	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 (Page No. 15 / Item No. 4.31)	Sqm	77.40	316.44	Rupees three hundred sixteen and paise forty four only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.